19. The lessee shall be held responsible for the occurrence of any fire within the State Forests if there is sufficient ground for the Forest Department to think that it has been caused by his negligence or by that of his employees.

20. The lessee shall furnish a list of sub-contractors and mestris who may be appointed by him for the collection of the produce.

21. Neither the lessee nor his men shall enter the State Forests either before sunrise or after sunset.

22. In the event of a breach of any of the above conditions, the lease is liable to be cancelled, all the produce collected to be confiscated and the lessee rendered liable to pay such penalty as the District Forest Officer deems fit at his discretion.

M. A. VARADACHAR,
*District Forest Officer.*

## ENGINEERING DEPARTMENT.

*Abstract Notification.*

The attention of the public is invited to the notification advertising the sale by public auction of about 270 matured Jali trees within the boundary line behind the bund of Bethamangala tank on the 6th November 1920, at 3 P.M., published in the issue of *Mysore Gazette*, dated 7th October 1920, Part VI, pages 628-629.

G. V. RAO,
*Executive Engineer, Water-Supply Division.*

*Notice dated 10th October* 1920.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 30th November 1920, for constructing a 3rd class Travellers' Bungalow at Yeslurpet, Manjarabad. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1922.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a 3rd Class Travellers' Bungalow at Yeslurpet, Manjarabad Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

## Detailed Abstract of quantities for constructing a 3rd class Travellers' Bungalow at Yeslurpet, Manjarabad Taluk.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| | MAIN BUILDING. | | |
| 1 | Earthwork excavation and filling basement | C. yd | 111 |
| 2 | Filling foundation with stone Jelly contrete in mortar | C. ft. | 829 |
| 3 | Burnt stone in mortar | " | 2,739 |
| 4 | Burnt Brick in mortar | " | 2,709 |
| 5 | Arch work in burnt brick in mortar | " | 28 |
| 6 | Teakwood work wrought and put up with wood oiling, etc., complete | " | 133·67 |
| 7 | Chunam plastering | Sq. | 40·82 |
| 8 | White and colour washing | " | 40·82 |
| 9 | Chunam pointing | " | 3·14 |
| 10 | Burnt stone slabs roughly dressed | S. ft. | 481 |
| 11 | Teakwood pannelled doors with frame, iron fastenings, lock, etc., complete | " | 158 |
| 12 | Teakwood pannelled doors with 4 shutters, frame, iron fastenings, lock, etc., complete. | " | 30 |
| 13 | Teakwood pannelled windows with frame, iron bars and fastenings, etc., outside pannelled and inside glazed. | " | 70 |
| 14 | Teakwood circular ventilators | " | 14 |
| 15 | Roofing with 1st class Mangalore tiles and teak reepers including fixing of eave tiles with nails and teak reepers. | Sq. | 19·41 |
| 16 | Ridge tiles set in mortar | R. ft. | 87 |
| 17 | Flooring with Mangalore tiles over 3" concrete bed and cement pointing | Sq. | 5·04 |
| 18 | Flooring with Cadappa slabs on 3" concrete bed and cement pointing | " | 4·78 |
| 19 | Ventilating tiles | No | 16 |
| 20 | Silicate, painting 2 coats | Sq. | 7·32 |
| 21 | Teakwoad eave board with wood oiling complete 1"x9" | R. ft. | 168 |
| 22 | Tarring to wood work | L. S. | Rs. |
| 23 | Clearing site, and levelling ground | " | " |
| 24 | Cornice work for pillars | R. ft. | 57 |
| | Teakwood battened door with fastening, etc. | " | 36 |
| | Constructing cisterns with $\frac{3}{8}$" thick with cement plastering inserting drain pipe, etc., complete. | L. S. | Rs. |

## Constructing a high caste native kitchen to the Travellers ' Bungalow at Yeslurpet.

| | | | |
|---|---|---|---|
| 1 | Earthwork excavating foundation and filling basement | C. yd. | 16 |
| 2 | Stone in mortar | C. ft. | 566 |
| 3 | Burnt brick in mortar | " | 1031 |
| 4 | Chunam plastering | Sq. | 19·00 |
| 5 | White and colour washing | " | 19·00 |
| 6 | Chunam pointing | " | 1·27 |
| 7 | Burnt brick in chunam arch work | C. ft. | 10 |
| 8 | Burnt stone slabs roughly dressed | S. ft. | 119 |
| 9 | Flooring with Mangalore tiles over 3" concrete bed and cement pointing | Sq. | 2·93 |
| 10 | Roofing with 1st class Mangalore titles on teak reepers including fixing eave tites with nails and teak reepers. | " | 7·40 |
| 11 | Chunam borders | R. ft. | 42 |
| 12 | Ridge tiles set in mortar | " | 29 |
| 13 | Ventilating tiles | No | 4 |
| 14 | Teakwood work wrought and put up with wood oiling complete | C. ft. | 31·80 |
| 15 | Teakwood battened doors with iron fastenings, etc., complete | S. ft. | 101 |
| 16 | Teakwood battened windows with iron bars, etc., complete | " | 9 |
| 17 | Teakwood eave board 1"+9" | R. ft. | 109 |
| 18 | Teakwood glazed ventilators | S. ft. | 22 |
| 19 | Tarring | L. S. | Rs. |
| 20 | Constructing fire place and chimney, etc., complete | " | " |
| 21 | Cleaning site and levelling ground and forming | " | " |
| 22 | Providing a mortar pestals stone | " | " |
| 23 | Providing pestal mortar and steps | " | " |
| 24 | Silicate painting two coats to doors and windows | Sq. | 3·50 |

## Constructing out-houses including mortor shed.

| | | | |
|---|---|---|---|
| 1 | Earthwork excavation and filling in basement | C. yd. | 44 |
| 2 | Concrete | C. ft. | 393 |
| 3 | Burnt stone in mortar | " | 857 |
| 4 | Burnt brick in mortar | " | 1,493 |
| 5 | Do arch work | " | 24 |
| 6 | Burnt stone slabs 6" thick | S. ft. | 102 |
| 7 | Teakwood work wrought and put up with painting, etc., complete | C. ft. | 56·24 |
| 8 | Roofing with 1st class Mangalore tiles on teak reepers | Sq. | 11·72 |
| 9 | Ridge tiles set in mortar | R. ft. | 60 |
| 10 | Chunam borders | " | 34 |
| 35 | Chunam plastering | Sq. | 27·50 |
| 36 | White and colour washing 2 coats | " | 27·50 |
| 37 | Chunam pointing | " | 1 00 |
| 38 | Teakwood battened doors including iron works, painting, etc., complete | S. ft. | 18 |
| 39 | Teakwood battened windows including iron bars, pointing, etc , complete | " | 8 |
| 40 | Flooring with gravel including watering and tamping and cowdung washing etc, complete. | C. yd. | 4 |
| 41 | Providing gate way for mortar shed including painting, etc., complete | S. ft. | 74 |
| 42 | Flooring with Kadappa slabs over 3" concrete bed and cement painting | Sq. | 3·00 |
| 43 | Providing thick bamboos for stable | L. S. | Rs. |
| 44 | Clearing site and levelling ground filling ditches, tarring to wood work, etc. | " | Rs. |
| 45 | Teakwood plank 1½" thick | S. ft. | 25 |
| 46 | Tarring wood work | L. S. | Rs. |

Constructing a latrine to the Travellers' Bungalow at Yeslurpet.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 1 | Earthwork excavation | C. yd. | 4 |
| 2 | Burnt stone in mortar | C. ft. | 113 |
| 3 | Burnt brick in mortar | Do | 249 |
| 4 | Constructing seats with cement plastering | L. S. | Rs. |
| 5 | Burnt stone slabs 6" thick | S. ft. | 5 |
| 6 | Jungle wood work wrought and put up | C. ft. | 4·02 |
| 7 | Coping 9" burnt brick in chunam with plastering | R. ft. | 8 |
| 8 | Cornice work 6" | Do | 26 |
| 9 | Honne wood cross pieces for ventilators | L. S. | L. S. |
| 10 | Roofing with 1st class Mangalore tiles and teak reepers | Sq. | 0·93 |
| 11 | Chunam plastering | Sq. | 4·82 |
| 12 | White and colourwashing | Do | 4·19 |
| 13 | Tarring | L. S. | 5 |
| 14 | Constructing surki drain and cement plastering | L. S. | 10 |
| 15 | Flooring with concrete in mortar 3" and cement plastering | Sq. | 0·33 |
| | Sinking a well in the compound | L. S. | Rs. |

K. NARYANA IYENGAR,
*Ex. Engr. Hassan Division.*

## CHITALDRUG DIVISION.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 5th November 1920, for restoring the Gudanurahalli large minor tank Registered No. 2 of Hiriyur Taluk, Chitaldurg District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

| Description of work | Unit of work | Rate per unit |
|---|---|---|
| | | |

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Gudanurahalli large minor tank, Registered No. 2 of Hiriyur Taluk, Chitaldrug District, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Gudanurahalli large minor tank, Registered No. 2 of Hiriyur Taluk, Chitaldrug District.

| No. | Items of work | Quantity | |
|---|---|---|---|
| | *Bund*— | | |
| 1 | Earthwork with watering, tamping, etc.; complete ... | C. yd. | 2,819 |
| 2 | Providing new stone revetment with new jelly, backing ... | C. yd. | 609 |
| 3 | New grade stones with figures cut and painted ... ... | No. | 24 |
| 4 | New top width stones ... ... ... ... | No. | 24 |
| 5 | Providing new gauge stone with figures cut and painted ... | No. | 1 |
| 6 | Providing new bench mark stones with figures and painting | No. | 1 |
| | *Sluice*— | | |
| 7 | Cutting open the bund and examining and repairing the sluice including refilling. | L. S. | Rs. |
| | *Weir*— | | |
| 8 | Earthwork excavation hard soil ... ... ... | C. yd. | 1,035 |
| 9 | Pitching rough stone apron ... ... ... | C. yd | 292⅓ |
| 10 | Burnt stone toe slabs ... ... ... ... | S. ft. | 390 |